


- A. LANDSCAPE PRODUCTS VALVE BOX WITH DRIP REMOTE CONTROL ZONE KIT
- B. IRRIGATED LANDSCAPE AREA WITH SETBACK ($\pm 2"-4"$)
- C. LANDSCAPE PRODUCTS 17MM EZ-ID CV COLOR CODED DRIPLINE (NOTE: TOTAL FLOW FOR THIS LAYOUT SHOULD NOT EXCEED 5 GPM)
- D. 17MM INSERT FITTING (TYPICAL)
- E. FLUSH POINT



17MM EZ-ID CV DRIPLINE 'E-ZEE' LAYOUT
NOT TO SCALE

Single Lateral Maximum Run Length (Feet)						
Inlet Pressure (psi)	12" Spacing			18" Spacing		
	Nominal Flow (gph)			Nominal Flow (gph)		
	0.4	0.6	1.0	0.4	0.6	1.0
15	220	170	125	285	240	170
25	326	255	195	495	370	275
35	410	330	238	572	470	335
45	474	360	270	640	515	375

17MM EZ-ID CV DRIPLINE 'E-ZEE' LAYOUT - March 2, 2015